CHITALDRUG DISTRICT.

Abstract Notification, dated 3rd—4th August 1933.

The attention of the public is drawn to this office detailed Notification, dated 3rd August 1933, regarding the sales of fuel coupes in the District for 33-34, commencing from 4th September 1933, published on pages 1041–42, Part VI of the *Mysore Gazette*, dated 17th August 1933.

B. N. IYENGAR,
District Forest Officer.

ENGINEERING DEPARTMENT.

OFFICE OF THE EXECUTIVE ENGINEER, BUILDINGS DIVISION, BANGALORE.

Abstract Notification, dated 14th August 1933.

The attention of the public is invited to the notification calling for tenders for "Construction of a Building for the Technological Institute, Bangalore, published on pages 1036 to 1040, Part VI of the *Mysore Gazette*, dated 17th August 1933

The last date for receiving tenders is 6th September 1933.

A. TANDONI RAO,
Executive Engineer.

BANGALORE DIVISION.

Abstract Notification dated 7th August 1933.

The attention of the public is hereby invited to the detailed notification inviting tenders for the work of Restoring of Korati Urumundinakere Regd. No. 15—626 of Hoskote Taluk, published on pages 1010 and 1011 of Part VI of the *Mysore Gazette*, dated 10th August 1933.

The last day for the receipt of tenders is 2 P.M., precisely on 28th August 1933.

The earnest money to accompany the tender is Rs. 300.

Abstract Notification, dated 31st July 1933.

The attention of the public is hereby invited to the detailed notification inviting tenders for the work of Constructing an additional shed for holding carpentry and weaving classes attached to the Government School at Anekal, published on pages 989 and 990 of Part VI of the *Mysore Gazette*, dated 10th August 1933.

2. The last date for the receipt of tenders is 2 P.M. of 28th August 1933 and the earnest money to accompany the tender is Rs. 200.

M. A. SRINIVASACHARI,
Executive Engineer.

KOLAR DIVISION.

Abstract Notification, dated 1st August 1933.

The attention of the public is invited to the advertisement published in pages 994 and 995 of Part VI of the *Mysore Gazette*, dated 10th August 1933, calling for tenders for the work of Improving the Gottikere Tank, Regd. No. 273 of Srinivaspur Taluk.

The last date fixed for the receipt of tenders in this Office is 4th September 1933, up to 2 P.M.

Abstract Notification, dated 1st August 1933.

The attention of the public is invited to the advertisement published in pages 993 and 994 of Part VI of the *Mysore Gazette*, dated 10th August 1933, calling for tenders for the work of Restoring Thimmanaikanahalli Nagalkere, Sidlaghatta Taluk.

The last date fixed for the receipt of tenders in this Office is 30th August 1933, up to 2 P.M.

Abstract Notification, dated 1st August 1933.

The attention of the public is invited to the advertisement published in pages 991 and 992, Part VI of the *Mysore Gazette*, dated 10th August 1933, calling for tenders for the work of Restoring Vangimallu Tank Regd. No. 195 of Chintamani Taluk.

The last date fixed for the receipt of tenders in this Office is 30th August 1933 up to 2 P.M.

Abstract Notification. dated 1st August 1933.

The attention of the public is invited to the advertisement published in page 996, Part VI of the *Mysore Gazette*, dated 10 August 1933, calling for tenders for the work of Restoring Sadalvarapalli Oorumundinakere Regd. No. 718 of Bagepalli Taluk.

The last date fixed for the receipt of tenders in this Office is 28th August 1933, up to 2 P.M.

Abstract Notification, dated 1st August 1933.

The attention of the public is invited to the advertisement published in pages 990 and 991, Part VI of the *Mysore Gazette*, dated 10th August 1933, calling for tenders for the work of opening a feeder channel to the Minakankurki Tank Regd. No. 88 of Goribidnur Taluk.

The last date fixed for the receipt of tenders in this Office is 28th August 1933, up to 2 P.M.

Notification dated 14th August 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., on 11th September 1933, for Improving the feeder channel to Thirumani Tank, Reg. No. 42 of Gudibanda Sub-Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4 Each tender must be accompanied by a deposit of Rupees four hundred and fifty in cash or Government Currency Notes, as earnest money, and be superscribed "Tender for Improving the feeder channel to Thirumani Tank, Regd. No. 42 of Gudibanda Sub-Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders, will be returned.

9. Rates should be entered both in words and figures.

Abstract estimate of the probable cost of Improving the existing feeder Channel to Thirumani Tank from Thirumani ane of Chitravaty River, Gudibanda Sub-Taluk.

No.	Items of work	Per	Quantity	Rate	Cost
				Rs. a. p.	Rs.
1	Earth work excavation in hard soil and putting enbankment on lower side and forming.	C.yds.	10,835	0 5 0	3,386
2	Earth work excavation in ordinary soil, etc., complete.	,,	15,609	0 4 0	3,902
3	Jungle clearing and root removal ...	Fur.	14	50 0 0	700
4	Cutting bund and refilling and providing additional vent. of 2' x 2½' with shutter for existing vent. of 1½' x 2' and proposed vent. of 2' x 2½'.	Lump sum		...	450
5	Providing 4" diameter pipe for Irrigation directly under the Channel (C. I. pipe).	Lump sum		...	50
6	Mile and zero stones with dressing and painting complete.	2	Each	8 0 0	16
7	Grade stones do on bank ..	43	,,	2 0 0	86
8	Bed grade stones	43,	,,	2 8 0	108
	Total Rupees ..	...	...	...	8,698

Notification, dated 14th August 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 11th September 1933, for the work of Restoring (Yellampalli) Maddalkana Gowdankere Minor Tank, Reg. No. 526, Kasaba Hobli, Bagepalli Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees one hundred and thirty in cash or Government Currency Notes as earnest money and be superscribed "Tender for the work of Restoring Yellampalli Maddalkana Gowdankere Minor Tank, Registered No. 526 Kasaba Hobli, Bagepalli Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be written both in words and figures.

Abstract Estimate for Restoring Yellampalli Maddalkana Gowdanakere, Minor Tank Reg. No. 526 Kasaba Hobli, Bagepalli Taluk.

No.	Items of work	Per	Quantity	Rate	Amount
	Bund Filling in breach.			Rs. a. p.	Rs.
1	Earth work excavation foundation for Corewall in Soft Rock R. L. 48·00.	C.yds.	5	1 0 0	5
2	Burnt brick in Surki mortar for Corewall from R. L. 48·00 to 52·00.	C.ft.	225	0 5 0	70
	Or				
2a	Stone in surki mortar per Do ...	„	„	„	
3	Earth work filling in breach including watering and tamping.	C.yds.	283	0 5 0	88
4	Rough stone revetment new ...	„	55	1 12 0	96
5	Fanal Backing ...	„	28	0 12 0	21
6	Cutting Steps and grips ...	L. S.	..	..	10
7	Turfing	S.yd.	269	0 1 0	17
8	Earth work to bund, watering and tamping.	C.yd.	3,835	0 4 0	959
9	Turfing to bund ...	S.yd.	5,005	0 1 0	313
10	Re-setting old stone work ...	C.yd.	75	0 12 0	57
11	New Stone work ...	„	145	1 12 0	254
12	Jungle clearing, including removal of roots, from 3 to 11 grades.	Grade	L. S.	...	10
13	Providing grade stones, cutting figures and painting complete.	No.	14	1 8 0	21
14	Providing Index stones, Cutting figures and painting complete.	„	14	0 8 0	7
15	Providing new Register, number and date stone, cutting figures and painting complete.	„	1	3 0 0	3

No.	Items of work	Unit	Quantity	Rate	Amount
				Rs. a. p.	Rs.
16	Providing bench mark stones, and cutting figures and painting complete.	No.	2	3 0 0	6
17	Providing gauge stone, cutting figures and painting complete.	„	1	15 0 0	15
18	Cutting grips 3 $\frac{1}{2}$ x 3' for the seat of new earth work, removing ant hills and forming slopes.	Grade	13	3 0 0	39
19	Sundry and unforeseen works	Lump sum		...	11
20	Jelly wedging the old stone work wherever necessary.	„	„	...	65
	Total Rupees ...	...	...	...	2,067
	Sluice				
1	Cutting the bund and examining the leaks in the breach, repairing and filling and locking arrangements complete.	Lump sum			150
	Waste Weir.				
1	Stone jelly Concrete in surki ..	C.ft.	491	0 4 0	123
2	Burnt brick in surki ...	„	407	0 5 0	127
	Or				
2a	Stone in surki mortar ...	„	407	...	...
3	Burnt stone slabs 6" thick new, including gobble joints.	S.ft.	140	0 5 0	44
4	Burnt stone slabs old including joggle joints.	„	153	0 2 0	15
5	New stone apron with jelly wedging ...	C.yd.	34	1 12 0	60
6	Resetting old stone apron ...	„	7	0 12 0	5
7	Plastering with surki mortar ...	Sqr.	6·87	4 0 0	27
8	Sundry and unforeseen works including Cement binding to carved apron.	Lump sum		...	7
	Total Rupees ...	..	...	...	412

General Abstract.

		Rs.
1.	Total to Bund ...	2,067
2.	„ Sluice ...	150
3.	„ Waste weir ...	412
	Total ..	2,629

C. T. NARASIMHA IYENGAR
Executive Engineer.

EXECUTIVE ENGINEER'S OFFICE, MYSORE RAILWAYS, MYSORE.

Notification dated 11th August 1933.

The attention of the public is invited to the detailed notifications calling for tenders for:

(1) the construction of pits in the Engine erection Shop, and

(2) the construction of extension to New Machine Shop in the Central Workshop's area, Mysore, published on pages 997-1000 of Part VI of the *Mysore Gazette*, dated 10th August 1933. The last dates for receiving tenders are the 26th and 25th August 1933 up to 4 P.M. respectively.

R. N. MIRZA,
Senior Executive Engineer.